



TOWN OF NORTH CASTLE

WESTCHESTER COUNTY
17 Bedford Road
Armonk, New York 10504-1898

RESIDENTIAL PROJECT
REVIEW COMMITTEE
Adam R. Kaufman AICP, Chair

Telephone: (914) 273-8625
Fax: (914) 273-3554
www.northcastleny.com

RPRC DETERMINATION LETTER

Project Name: GOLDENBERG - Pool
Street Location: 3 REDBROOKE PL
Zoning District: R-2A Property Acreage: 2.02 Tax ID: 101.04-1-19
RPRC DECISION: ☐ Requires Planning Board Review ☐ Requires Architectural Review Board
☐ Requires Conservation Board ☐ Requires Zoning Board of Appeals
☒ Submit to Building Department ☐ Requires Admin Wetlands Permit
Date: December 20, 2017

The above referenced application was reviewed by the Residential Project Review Committee (RPRC) on December 19, 2017.

The Committee determined that Planning Board and Architectural Review Board approval of the proposed project is NOT REQUIRED.

However, the following issues will need to be addressed prior to the issuance of a building permit:

- The Applicant shall submit gross land coverage backup data for review.
- The site plan shall be revised to depict the location of the proposed 4' high black vinyl chain link fence.
- Show the location of the new pool fence.
- Show any walkway connections from the pool to the house.
- Show any existing trees and include any proposed landscaping and screening.
- The plan shall illustrate and quantify the limits of disturbance. The plan shall note that disturbance limits shall be staked in the field prior to construction.
- Show proposed grading for the pool and show any required retaining walls.
- The applicant shall perform deep and percolation soil testing to be witnessed by the Town Engineer. The test locations and results shall be shown on the plan. Contact the Town Engineer to schedule the testing.
- Provide stormwater mitigation design calculations for the runoff generated by the 25-year storm for the net increase in impervious surface or a 6 inch pool drawdown volume; whichever is greater. Provide details of the stormwater mitigation system.
- Provide rims, inverts, size and material for all drainage facilities. Provide details.
- Show the connection between the pool equipment and drawdown mitigation practice.

- Include erosion control measures on the plan, including, but not limited to, temporary construction access, silt fence, inlet protection, tree protection, erosion control blankets, construction sequence, etc. Provide details.
- Show the location of the existing septic primary and expansion areas on the plan. The plan shall show this area to be cordoned off during construction.

At this time you may coordinate directly with the North Castle Building Department. **DO NOT START CONSTRUCTION WITHOUT A VALID BUILDING DEPARTMENT PERMIT.**

If you would like to further discuss this matter, please do not hesitate to contact the Building Department.

Adam R. Kaufman, AICP
Director of Planning