

TOWN OF NORTH CASTLE

WESTCHESTER COUNTY 17 Bedford Road Armonk, New York 10504-1898

RESIDENTIAL PROJECT REVIEW COMMITTEE Adam R. Kaufman AICP, Chair Telephone: (914) 273-8625 Fax: (914) 273-3554 www.northcastleny.com

RPRC DETERMINATION LETTER

x ID: 108.02-1-70	
☐ Requires Architectural Review Board	
☐ Requires Zoning Board of Appeals	
☐ Requires Admin Wetlands Permit	
)1 ()	

The above referenced application was reviewed by the Residential Project Review Committee (RPRC) on May 2, 2017.

The Committee determined that Planning Board and Architectural Review Board approval of the proposed project is NOT REQUIRED.

However, the following issues will need to be addressed prior to the issuance of a building permit:

- All proposed curb cuts shall have an 18 foot maximum width.
- The plan shall illustrate and quantify the limits of disturbance. The plan shall note that disturbance limits shall be staked in the field prior to construction.
- Show all required minimum yard setbacks on the plan.
- Provide construction details for all proposed improvements, including, but not limited to, driveway, drainage, curbing, walkways, erosion controls, patio, etc.
- The Site Plan should show proposed topography.
- Show the location of the existing utilities (septic, etc.). Demonstrate that the required setbacks to the stormwater mitigation system are met.
- The applicant shall perform deep and percolation soil testing to be witnessed by the Town Engineer. The test locations and results shall be shown on the plan. Contact the Town Engineer to schedule the testing.
- Provide stormwater mitigation and design calculations for the runoff generated by the 25-year storm for the net increase in impervious surface. Provide details of the stormwater mitigation system.
- Provide rims, inverts, size and material for all drainage facilities. Provide details.
- All trees 8 inches dbh or greater located within or 10 feet beyond the proposed limit of disturbance shall be shown on the plan. Indicate trees to be removed and/or protected.

• Include erosion control measures on the plan, including, but not limited to, temporary construction access, silt fence, inlet protection, tree protection, erosion control blankets, construction sequence, etc. Provide details.

At this time you may coordinate directly with the North Castle Building Department. DO NOT START CONSTRUCTION WITHOUT A VALID BUILDING DEPARTMENT PERMIT.

If you would like to further discuss this matter, please do not hesitate to contact the Building Department.

Adam R. Kaufman, AICP Director of Planning