



# TOWN OF NORTH CASTLE

WESTCHESTER COUNTY  
17 Bedford Road  
Armonk, New York 10504-1898

RESIDENTIAL PROJECT  
REVIEW COMMITTEE  
Adam R. Kaufman AICP, Chair

Telephone: (914) 273-8625  
Fax: (914) 273-3554  
www.northcastleny.com

## RPRC DETERMINATION LETTER

Project Name: ABRAHAM - Addition  
Street Location: 7 NORTH LN  
Zoning District: R-1A Property Acreage: 1 Tax ID: 101.02-3-5  
RPRC DECISION: ☐ Requires Planning Board Review ☐ Requires Architectural Review Board  
☐ Requires Conservation Board ☐ Requires Zoning Board of Appeals  
☒ Submit to Building Department ☐ Requires Admin Wetlands Permit  
Date: March 18, 2015

---

The above referenced application was reviewed by the Residential Project Review Committee (RPRC) on March 17, 2015.

The Committee determined that Planning Board and Architectural Review Board approval of the proposed project is NOT REQUIRED.

However, the following issues will need to be addressed prior to the issuance of a building permit:

- The proposed second floor addition on GFA worksheet does not match other submitted information. The Applicant shall submit revised GFA and GLC backup information.
- The Building Inspector shall determine whether Health Department review would be required.
- The site plan shall be revised to depict screening for the western property line to the satisfaction of the Town Engineer.
- The plan shall illustrate and quantify the limits of disturbance. The plan shall note that disturbance limits shall be staked in the field prior to construction.
- Show all required minimum yard setbacks on the plan.
- Show all existing site improvements (pool, septic, drainage, infiltration, etc.).
- The applicant shall perform deep and percolation soil testing to be witnessed by the Town Engineer. The test locations and results shall be shown on the plan. Contact this office to schedule the testing.
- Provide stormwater mitigation and design calculations for the runoff generated by the 25-year storm for the net increase in impervious surface. Provide details of the stormwater mitigation system.
- Include erosion control measures on the plan, including, but not limited to, temporary construction access, silt fence, inlet protection, tree protection, erosion control blankets, construction sequence, etc. Provide details.

At this time you may coordinate directly with the North Castle Building Department. DO NOT START CONSTRUCTION WITHOUT A VALID BUILDING DEPARTMENT PERMIT.

If you would like to further discuss this matter, please do not hesitate to contact the Building Department.