



# TOWN OF NORTH CASTLE

WESTCHESTER COUNTY  
17 Bedford Road  
Armonk, New York 10504-1898

RESIDENTIAL PROJECT  
REVIEW COMMITTEE  
Adam R. Kaufman AICP, Chair

Telephone: (914) 273-8625  
Fax: (914) 273-3554  
www.northcastleny.com

## RPRC DETERMINATION LETTER

Project Name: LORBERBAUM - Pool  
Street Location: 31 MIDDLE PATENT RD  
Zoning District: R-1.5A Property Acreage: 6.17 Tax ID: 102.01-1-2  
RPRC DECISION: ☐ Requires Planning Board Review ☐ Requires Architectural Review Board  
☐ Requires Conservation Board ☐ Requires Zoning Board of Appeals  
☒ Submit to Building Department ☐ Requires Admin Wetlands Permit  
Date: March 3, 2016

---

The above referenced application was reviewed by the Residential Project Review Committee (RPRC) on March 1, 2016.

The Committee determined that Planning Board and Architectural Review Board approval of the proposed project is NOT REQUIRED.

However, the following issues will need to be addressed prior to the issuance of a building permit:

- The site plan should include existing and proposed topography and proposed spot grades in pool area.
- Provide fence details, including height, material, etc. The plan shall delineate the limits of each fence type.
- The plan shall include a pool fence and gate detail.
- The plan shall illustrate and quantify the limits of disturbance. The plan shall note that disturbance limits shall be staked in the field prior to construction.
- Provide construction details for all proposed improvements, including, but not limited to, patio, drainage, curbing, walkways, erosion controls, etc.
- Provide stormwater mitigation design calculations for the runoff generated by the 25-year storm for the net increase in impervious surface or a 6 inch pool drawdown volume; whichever is greater. Provide details of the stormwater mitigation system.
- Show the connection between the pool equipment and drawdown mitigation practice.
- All trees 8 inches dbh or greater located within or 10 feet beyond the proposed limit of disturbance shall be shown on the plan. Indicate trees to be removed and/or protected.
- Include erosion control measures on the plan, including, but not limited to, temporary construction access, silt fence, inlet protection, tree protection, erosion control blankets, construction sequence, etc. Provide details.
- Show the location of the existing septic primary and expansion areas on the plan. The plan shall show this area to be cordoned off during construction.

At this time you may coordinate directly with the North Castle Building Department. DO NOT START CONSTRUCTION WITHOUT A VALID BUILDING DEPARTMENT PERMIT.

If you would like to further discuss this matter, please do not hesitate to contact the Building Department.

Adam R. Kaufman, AICP  
Director of Planning