



TOWN OF NORTH CASTLE

WESTCHESTER COUNTY
17 Bedford Road
Armonk, New York 10504-1898

RESIDENTIAL PROJECT
REVIEW COMMITTEE
Adam R. Kaufman AICP, Chair

Telephone: (914) 273-8625
Fax: (914) 273-3554
www.northcastleny.com

RPRC DETERMINATION LETTER

Project Name: TESTANI - Pool
Street Location: 70 WINDMILL RD
Zoning District: R-1.5A Property Acreage: 1.5 Tax ID: 102.03-1-5
RPRC DECISION: ☐ Requires Planning Board Review ☐ Requires Architectural Review Board
☐ Requires Conservation Board ☐ Requires Zoning Board of Appeals
☒ Submit to Building Department ☒ Requires Admin Wetlands Permit
Date: May 22, 2015

The above referenced application was reviewed by the Residential Project Review Committee (RPRC) on May 19, 2015.

The Committee determined that Planning Board and Architectural Review Board approval of the proposed project is NOT REQUIRED.

However, the following issues will need to be addressed prior to the issuance of a building permit:

- The Applicant shall submit gross land coverage backup information as proposal is at maximum permitted amount of GLC to the satisfaction of the Building Department.
- The plan shall include a note stating that "Walls greater than 4 feet in height shall be designed and certified by a NYS Professional Engineer". Provide details and specifications on the plan.
- The plan shall illustrate and quantify the limits of disturbance. The plan shall note that disturbance limits shall be staked in the field prior to construction.
- The applicant shall perform deep and percolation soil testing to be witnessed by the Town Engineer. The test locations and results shall be shown on the plan. Contact the Town Engineer to schedule the testing.
- The rim elevations for the proposed drain inlets shall be verified. Provide rims, inverts, size and material for all drainage facilities. Provide details.
- Show the connection between the pool equipment and drawdown mitigation practice.
- All trees 8 inches dbh or greater located within or 10 feet beyond the proposed limit of disturbance shall be shown on the plan. Indicate trees to be removed and/or protected.
- Include erosion control measures on the plan, including, but not limited to, temporary construction access, silt fence, inlet protection, tree protection, erosion control blankets, construction sequence, etc. Provide details.
- The plan shall show the area of the existing septic primary and expansion areas to be cordoned off during construction.

- It appears that disturbances are proposed within the locally-regulated 100 foot wetland buffer of an off-site stream. A local Administrative Wetland Permit may be required. The applicant shall illustrate the local wetland boundary and regulated 100 foot buffer on the plan for verification by the Town Wetland Consultant. Notify the Town Engineer once the wetland boundary has been established in the field.

At this time you may coordinate directly with the North Castle Building Department. **DO NOT START CONSTRUCTION WITHOUT A VALID BUILDING DEPARTMENT PERMIT.**

If you would like to further discuss this matter, please do not hesitate to contact the Building Department.

Adam R. Kaufman, AICP
Director of Planning