

TOWN OF NORTH CASTLE

WESTCHESTER COUNTY 17 Bedford Road Armonk, New York 10504-1898

RESIDENTIAL PROJECT REVIEW COMMITTEE Adam R. Kaufman AICP, Chair Telephone: (914) 273-8625 Fax: (914) 273-3554 www.northcastleny.com

RPRC DETERMINATION LETTER

Project Name:	ZELTNER - Addition				
Street Location:	21 ELIZABETH PL				
Zoning District:	R-1A Property Acrea		ige: 0.46	Tax ID: 101.03-2-31	
RPRC DECISION:	☐ Requires Planning Board Review		☐ Requires Architectural Review Board		
	□ Requires Conservation Board■ Submit to Building Department		☐ Requires Zoning Board of Appeals		
			☐ Requires Admin Wetlands Permit		
Date:	April 22, 2015				

The above referenced application was reviewed by the Residential Project Review Committee (RPRC) on April 21, 2015.

The Committee determined that Planning Board and Architectural Review Board approval of the proposed project is NOT REQUIRED.

However, the following issues will need to be addressed prior to the issuance of a building permit:

- · Westchester County Health Department shall review the adequacy of the existing septic system.
- The plan shall illustrate and quantify the limits of disturbance. The plan shall note that disturbance limits shall be staked in the field prior to construction.
- · Show all required minimum yard setbacks on the plan.
- · Provide construction details for all proposed improvements, including, but not limited to drainage, walkways, erosion controls, etc.
- · Show the location of the existing utilities (water, septic, etc.). Demonstrate that the required setbacks to the infiltration system are met.
- The infiltration system shall be equipped with an emergency overflow.
- · Provide rims, inverts, size and material for all drainage facilities. Provide details.
- · All trees 8 inches dbh or greater located within or 10 feet beyond the proposed limit of disturbance shall be shown on the plan. Indicate trees to be removed and/or protected.
- · Include erosion control measures on the plan, including, but not limited to, temporary construction access, silt fence, tree protection, construction sequence, etc. Provide details.
- · Show the location of the existing septic primary and expansion areas on the plan. The plan shall show this area to be cordoned off during construction.

At this time you may coordinate directly with the North Castle Building Department. DO NOT START CONSTRUCTION WITHOUT A VALID BUILDING DEPARTMENT PERMIT.